



# CITY OF SAN ANTONIO

P.O. Box 839966  
San Antonio, Texas 78283-3966

## ADDENDUM III

SUBJECT: Heavy Equipment, 11-038 LD, Scheduled to Open: February 1, 2011; Date of Issue: December 30, 2010

FROM: Denise D. Gallegos, C.P.M., CPPB, Purchasing & Contracts Administrator

DATE: January 27, 2011


**This notice shall serve as Addendum No. III to the above-referenced Formal Invitation For Bid and shall become part of the original Bid package and must be returned with bid on or before the due date.**

### **THE ABOVE MENTIONED FORMAL INVITATION FOR BID IS HEREBY AMENDED AS FOLLOWS:**

1. Page 15, Item 2, Paragraph 9, Change paragraph to read: "Safety Equipment - OSHA standard ROPS/FOPS with safety screens on sides and include a rear window with safety screen to reduce engine noise, warning horn, backup alarm, starting safety mechanism, seat belt, hour meter and lifting eyes or hooks. Four work lights, two front mounted and two rear mounted. Unit shall have amber rotating or flashing warning beacon mounted to top of cab."
2. Addendum II, Page 2, Paragraph 17 for Item 7, Change paragraph to read: "Vandalism Protection Kit - Full vandalism protection for both chassis cab and upper cab to include medal window cover panels for all windows, engine side panels, lighting covers, fluid cap locking devices, battery box cover with locking device, tool box with locking device, instrument cover with locking device(s) and a complete set of locks with keys."
3. Addendum II, Page 2, Paragraph 18, added Item 8, Paragraph 1 of specifications, Change 1<sup>st</sup> sentence to read: " Engine – Diesel, water cooled, 4-cycle, minimum 56 SAE net h.p., spin on dry type oil filter, dry type air filter, minimum fuel capacity 20 gallons."
4. Addendum II, Page 3, Paragraph 18, added Item 8, Paragraph 6 of specifications, Change paragraph to read: "Performance Specifications – Operating weight minimum of 6,000 lb. without additional weights or filled tires, SAE rated operating load minimum of 1,750 lbs. If required, the proper amount of counterweights shall be provided."

5. Addendum II, Page 3, Paragraph 18 added Item 8, Paragraph 8 of specifications, Change 2<sup>nd</sup> sentence to read: "Unit shall have a breaker/hydraulic hammer assembly that shall be capable of a minimum 1150 blows per minute and shall have a tool diameter of a minimum 2.5" inches."
6. Addendum II, Page 3, Paragraph 18 added Item 8, Paragraph 9 of specifications, Change paragraph to read: "Safety Equipment - OSHA standard ROPS/FOPS with safety screens on sides and include a rear window to reduce engine noise, warning horn, backup alarm, starting safety mechanism, seat belt, hour meter and lifting eyes or hooks. Four work lights, two front mounted and two rear mounted. Unit shall have amber rotating or flashing warning beacon mounted to top of cab."
7. Addendum II, Page 4, Paragraph 19 added Item 9, Paragraph 7 of specifications, Change last sentence to read: "Bucket shall have a SAE minimum 3 cubic foot capacity."

**\*\*THIS ADDENDUM MUST BE SIGNED AND RETURNED WITH THE BID PACKAGE\*\***



Denise D. Gallegos, C.P.M., CPPB  
Purchasing & Contracts Administrator  
Purchasing & General Services Department

Date \_\_\_\_\_

Company Name \_\_\_\_\_

Address \_\_\_\_\_

City/State/Zip Code \_\_\_\_\_

\_\_\_\_\_  
Signature