

MACINA • BOSE • COPELAND and ASSOCIATES, INC
CONSULTING ENGINEERS AND LAND SURVEYORS

Texas Registered Engineering Firm F-784
1035 Central Parkway North, San Antonio, Texas 78232
(210) 545-1122 FAX (210) 545-9302
www.mbcengineers.com

ADDENDUM NO. 7

CITY OF SAN ANTONIO
CAPITAL IMPROVEMENTS MANAGEMENT SERVICES DEPARTMENT


PROJECT NAME: CULEBRA 58F PHASE IIB

DATE: JUNE 9, 2011

This addendum shall be included in and be considered part of the plans and specifications for the above named project. The contractor shall be required to sign an acknowledgement of the receipt of this addendum at the time he receives it and returns signed form with the bid package.

CIMS PROJECT NO.: 40-00050

This Addendum is for the sole purpose of answering some Bidder questions which were overlooked while preparing Addendum No. 6. See Attachment



Robert A. Liesman

ADDENDUM #7 ATTACHMENTS

Question: Will geotechnical tested trench compaction be required of the contractor for the sewer line installation since it is running within an easement and not under any pavement?

Answer: *YES*

Question: Will engineer staking / cut sheets by required be SAWS for the sewer since the line is becoming a replace in place?

Answer: *YES; grade control is critical.*

Question: The waste management plan states that topsoil placed within the ROW be obtained from outside the project limits. Can topsoil be salvaged from within the existing channel as long as it meets the COSA Item 515 specification requirements?

Answer: *Topsoil to be imported per plan*

Question: Can the impacted soil be loaded and hauled off in lieu of stockpiling if the landfill will accept it with no additional testing since classification testing has been performed by COSA?

Answer: *Impacted soils should remain on site. Any hauling not required by COSA will be at Contractor's expense.*

Question: Can the soil from the AOC that stays onsite be loaded and immediately moved to the fill location once all waste debris is removed instead of stockpiling it?

Answer: *Impacted soils not requiring special disposal are intended to be carried to the designated fill area, spread and compacted. The extent to which interim stockpiling might be required will be dictated by the material analysis and segregation process. Any hauling not required by COSA will be at Contractor's expense. SEE PREVIOUS QUESTION/ANSWER.*

Question: What is the color required for the anti-graffiti coating? As you can imagine, they have clear, then added material cost for standard colors and additional material cost for specialty colors?

Answer: *Anti-graffiti coating is clear. Color (if desired) will be added as admixture to the concrete.*

**CITY OF SAN ANTONIO
DEPARTMENT OF CAPITAL IMPROVEMENTS MANAGEMENT SERVICES
CONTRACT SERVICES DIVISION**

RECEIPT OF ADDENDUM NUMBER(S) 7 IS HEREBY ACKNOWLEDGED FOR PLANS AND SPECIFICATIONS FOR CONSTRUCTION OF CULEBRA 58F PHASE IIB

FOR WHICH BIDS WILL BE OPENED ON TUESDAY, JUNE 14, 2011 AT 2:00 PM

THIS ACKNOWLEDGEMENT MUST BE SIGNED AND RETURNED WITH THE BID PACKAGE.

Company Name: _____

Address: _____

City/State/Zip Code: _____

Date: _____

Signature

Print Name/Title

