PROPOSAL

TO

CITY OF SAN ANTONIO TEXAS

FOR THE CONSTRUCTION OF

Fort Sam Transportation Projects

IN SAN ANTONIO, TEXAS

The undersigned, as bidder, declares that the only person or parties interested in this proposal as principals are those named herein; that this proposal is made without collusion with any other person, firm, corporation; that Bidder has carefully examined the form of contract, instructions to bidders, profiles, grades, specifications, and the plans therein referred to, and has carefully examined the locations, conditions and classes of materials of the proposed work; and agrees that Bidder will provide all the necessary machinery, tools, apparatus, and other means of construction, and will do all the work and furnish all the materials called for in the contract and specifications in the manner prescribed therein and according to the requirements of the Director of Public Works as therein set forth.

It is understood that the following quantities of work to be done are approximate only, and are intended principally to serve as a guide in figuring out the bids.

It is understood and agreed that the work is to be completed in full in _____182___calendar days

Accompanying this Proposal is a Bid Guaranty in the amount of _____

_____ Dollars ($_____) said amount being _____ percent of the total bid. Said Bid Guaranty, in the form of a Certified or Cashier's Check on a State or National Bank, or Bid Bond, is submitted as a guaranty of the good faith of the Bidder and that the Bidder will execute and enter into a written contract to do the work, if his bid is accepted. It is hereby agreed that the Bidder may, at any time prior to opening of the bids withdraw this Proposal without penalty; it is also agreed that if Bidder shall, at any time after opening of bids, withdraw this Proposal or if this Bid is accepted and Bidder shall fail to execute the written contract and furnish satisfactory bond, within twenty (20) calendar days after the date of transmittal of the contract documents by Owner to Contractor, the City of San Antonio shall, in any of such events, be entitled and is hereby given the right to retain said Bid Guaranty as liquidated damages. It is understood that the City of San Antonio reserves the right to reject any and all bids whenever the City Council deems it in the interest of the City to do so, and also the right to waive any informalities in a bid.

In the event of the award of a contract to the undersigned, the undersigned will execute same on Standard Form City Construction Contract and make bond for the full amount of the contract, to secure proper compliance with the terms and provisions of the contract, and to insure and guarantee the work until final completion and acceptance or the end of the guarantee period where so stipulated, and to guarantee payment of all lawful claims for labor performed and materials furnished in the fulfillment of the contract.

The work proposed to be done shall be accepted when fully completed and finished to the entire satisfaction of the Director of Public Works.

The undersigned certifies that the bid prices contained in this proposal have been carefully checked and are submitted as correct and final.

Bidder is:

[] An individual proprietorship;

[] A partnership composed of _____

_____ and _____

[] A corporation chartered under the laws of the State of _____, acting by its officers pursuant to its by-laws or a resolution of its Board of Directors.

_____
(Name of Bidder)

By:_____
(Signature)

ATTEST:
Date

_____ _____
(Title)

Amount of Base Bid (Insert Amount in Words and Numbers): _____

_____

_____ $_____

Alternates (if applicable):

(1) _____ (3) _____

(2) _____ (4) _____

_____ _____
Company's Name Telephone No.

_____ _____
Address Fax No.

_____ _____
City & State Zip Code

CITY OF SAN ANTONIO
025 UNIT PRICING FORM

PROJECT NAME:
PROJECT NO.

ALT. NO.	ITEM NO.	DESC. CODE	S.P. NO	BID ITEM DESCRIPTION	UNIT OF MEASURE	APPROX. QUANTITIES	UNIT BID PRICE	AMOUNT	ITEM SEQUENCE NO.
	100	2002	2	PREPARING ROW	STA	68.35			
	104	2001	0	REMOVING CONC (PAV)	SY	5517			
	104	2017	0	REMOVING CONC (DRIVEWAYS)	SY	4891			
	104	2029	0	REMOVING CONC (CURB OR CURB & GUTTER)	LF	7600			
	104	2031	0	REMOVING CONC (HEADWALL)	CY	789			
	104	2036	0	REMOVING CONC (SIDEWALK OR RAMP)	SY	311			
	105	2011	0	REMOVING STAB BASE AND ASPH PAV (2"-6")	SY	26984			
	110	2001	0	EXCAVATION (ROADWAY)	CY	5751			
	112	2001	0	SUBGRADE WIDENING (ORD COMP)	STA	30.35			
	132	2001	0	EMBANKMENT (FINAL)(ORD COMP)(TY A)	CY	37932.9			
	162	2002	0	BLOCK SODDING	SY	15367.22			
	168	2001	0	VEGETATIVE WATERING	MG	251.128632			
	260	2001	2	LIME (HYDRATED LIME (DRY))	TON	1619.31			
	260	2006	2	LIME TRT (EXST MATL) (6")	SY	43067.78			
	316	2028	16	ASPH(AC-5 OR 10,CRS/HFRS-2,RS/CRS-1P)	GAL	16195.29			
	316	2582	16	AGGR (TY-PB GR-4)	CY	539.83			
	340	2236	3	D-GR HMA(METH) TY-B PG64-22 (LEVEL UP)	TON	749			
	341	2011	24	D-GR HMA(QCQA) TY-B PG64-22	TON	26695.31			
	341	2034	24	D-GR HMA(QCQA) TY-C PG64-22	TON	5938.28			
	354	2045	0	PLANE ASPH CONC PAV (2")	SY	13619			
	356	2024	0	PAV JT UNDERSEAL (48")	LF	5550			
	401	2001	0	FLOWABLE BACKFILL	CY	420			
	402	2001	0	TRENCH EXCAVATION PROTECTION	LF	3900			
	416	2031	0	DRILL SHAFT (TRF SIG POLE) (30 IN)	LF	12			
	416	2032	0	DRILL SHAFT (TRF SIG POLE) (36 IN)	LF	94			
	416	2034	0	DRILL SHAFT (TRF SIG POLE) (48 IN)	LF	44			
	420	2120	2	CL C CONC (BUS STOP)	CY	556.49			
	432	2001	0	RIPRAP (CONC)(4 IN)	CY	22.3708642			
	462	2006	0	CONC BOX CULV (5 FT X 2 FT)	LF	126			
	462	2019	11	CONC BOX CULV (8 FT X 4 FT)	LF	785			
	464	2005	3	RC PIPE (CL III)(24 IN)	LF	398			
	464	2007	3	RC PIPE (CL III)(30 IN)	LF	44			
	464	2009	3	RC PIPE (CL III)(36 IN)	LF	492			
	464	2011	3	RC PIPE (CL III)(48 IN)	LF	1110			

CITY OF SAN ANTONIO
025 UNIT PRICING FORM

PROJECT NAME:
PROJECT NO.

ALT. NO.	ITEM NO.	DESC. CODE	S.P. NO	BID ITEM DESCRIPTION	UNIT OF MEASURE	APPROX. QUANTITIES	UNIT BID PRICE	AMOUNT	ITEM SEQUENCE NO.
	464	2013	3	RC PIPE (CL III)(60 IN)	LF	193			
	465	2014	1	MANH (COMPL)(JUNCT BOX)	EA	14			
	465	2020	1	INLET (COMPL)(CURB)(TY II)	EA	17			
	465	2077	1	INLET (COMPL)(DROP)(TY 1)	EA	2			
	465	2211	1	JUNCTION BOX (SPL)	EA	7			
	465	2215	1	INLET (COMPL)(TY H)(SPL)	EA	1			
	465	2405	1	INLET (COMPL)(CURB)(TY C)	EA	1			
	465	2473	1	INLET EXT (TY II-E)	EA	31			
	465	2474	1	INLET EXT (TY C-E)	EA	2			
	465	xxxx	1	INLET (COMPL)(DROP)(TY 1A)	EA	1			
	500	2001	5	MOBILIZATION	LS	1			
	502	2001	33	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	10			
	502	2047	33	OFF-DUTY POLICE OFFICER	HR	288			
	506	2016	13	CONSTRUCTION EXITS (INSTALL) (TY 1)	SY	234			
	506	2019	13	CONSTRUCTION EXITS (REMOVE)	SY	156			
	506	2032	13	SANDBAGS FOR EROSION CONTROL (18")	LF	699			
	506	2034	13	TEMPORARY SEDIMENT CONTROL FENCE	LF	144			
	508	2002	0	CONSTRUCTING DETOURS	SY	8084			
	512	2008	2	PORT CTB (FUR & INST)(LOW PROF)(TY 1)	LF	3380			
	512	2009	2	PORT CTB (FUR & INST)(LOW PROF)(TY 2)	LF	240			
	512	2026	2	PORT CTB (MOVE)(LOW PROF)(TY 1)	LF	5580			
	512	2027	2	PORT CTB (MOVE)(LOW PROF)(TY 2)	LF	400			
	512	2044	2	PORT CTB (REMOVE)(LOW PROF)(TY 1)	LF	3380			
	512	2045	2	PORT CTB (REMOVE)(LOW PROF)(TY 2)	LF	240			
	529	2001	0	CONC CURB (TY I)	LF	12096			
	530	2010	0	DRIVEWAYS (CONC)	SY	4180			
	531	2008	0	CURB RAMPS (TY 4)	EA	13			
	531	2015	0	CONC SIDEWALK (4")	SY	3161.53			
	531	2034	0	CONC SIDEWALK (DRAIN)	LF	14			
	531	2040	0	CURB RAMPS (TY 5)	EA	3			
	536	2004	0	CONC DIRECTIONAL ISLAND	SY	718			

CITY OF SAN ANTONIO
025 UNIT PRICING FORM

PROJECT NAME:
PROJECT NO.

	618	2018	0	CONDT (PVC) (SCHD 40) (2")	LF	253			
	618	2022	0	CONDT (PVC) (SCHD 40) (3")	LF	1487			
	620	2009	1	ELEC CONDR (NO. 6) BARE	LF	31			

ALT. NO.	ITEM NO.	DESC. CODE	S.P. NO	BID ITEM DESCRIPTION	UNIT OF MEASURE	APPROX. QUANTITIES	UNIT BID PRICE	AMOUNT	ITEM SEQUENCE NO.
	620	2010	1	ELEC CONDR (NO. 6) INSULATED	LF	50			
	620	2011	1	ELEC CONDR (NO. 8) BARE	LF	1499			
	621	2002	0	TRAY CABLE (3 CONDR) (12 AWG)	LF	1640			
	624	2014	14	GROUND BOX TY D (162922) W/APRON	EA	11			
	628	2148	3	ELC SRV TY T 120/240 000 (NS)GS(N)SP(U)	EA	3			
	636	2001	14	ALUMINUM SIGNS (TY A)	SF	30			
	644	2060	0	REMOVE SM RD SN SUP & AM	EA	18			
	644	XXX1	0	INS SM RD SN SUP&AM COSA TY U MOUNT (POST TY 1)	EA	43			
	644	XXX2	0	INS SM RD SN SUP&AM COSA TY U MOUNT (POST TY 2)	EA	2			
	647	2002	0	RELOCATE LRSA	EA	2			
	662	2001	0	WK ZN PAV MRK NON-REMOV (W) 4" (BRK)	LF	6270			
	662	2004	0	WK ZN PAV MRK NON-REMOV (W) 4" (SLD)	LF	30810			
	662	2011	0	WK ZN PAV MRK NON-REMOV (W) 8" (LNDP)	LF	408			
	662	2012	0	WK ZN PAV MRK NON-REMOV (W) 8" (SLD)	LF	405			
	662	2016	0	WK ZN PAV MRK NON-REMOV (W) 24" (SLD)	LF	452			
	662	2032	0	WK ZN PAV MRK NON-REMOV (Y) 4" (SLD)	LF	25450			
	666	2003	0	REFL PAV MRK TY I (W) 4" (BRK)(100MIL)	LF	3640			
	666	2012	0	REFL PAV MRK TY I (W) 4" (SLD)(100MIL)	LF	8622			
	666	2015	0	REFL PAV MRK TY I (W) 6" (BRK)(100MIL)	LF	118			
	666	2033	0	REFL PAV MRK TY I (W) 8" (LNDP)(100MIL)	LF	205			
	666	2036	0	REFL PAV MRK TY I (W) 8" (SLD)(100MIL)	LF	9657			
	666	2048	0	REFL PAV MRK TY I (W) 24"(SLD)(100MIL)	LF	1785			
	666	2054	0	REFL PAV MRK TY I (W) (ARROW) (100MIL)	EA	36			
	666	2057	0	REFL PAV MRK TY I (W)(BIKE ARW)(100MIL)	EA	18			
	666	2063	0	REFL PAV MRK TY I(W)(BIKE SYML)(100MIL)	EA	18			
	666	2072	0	REFL PAV MRK TY I(W)(ENTR GORE)(100MIL)	EA	3			
	666	2075	0	REFL PAV MRK TY I(W)(EXIT GORE)(100MIL)	EA	2			
	666	2096	0	REFL PAV MRK TY I (W) (WORD) (100MIL)	EA	10			
	666	2099	0	REF PAV MRK TY I(W)18"(YLD TRI)(100MIL)	EA	2			
	666	2111	0	REFL PAV MRK TY I (Y) 4" (SLD)(100MIL)	LF	18552			

CITY OF SAN ANTONIO
025 UNIT PRICING FORM

PROJECT NAME:
PROJECT NO.

	666	2132	0	REFL PAV MRK TY I (Y) 24"(SLD)(100MIL)	LF	2539			
	666	2141	0	REFL PAV MRK TY I (Y)(MED NOSE)(100MIL)	EA	12			
	666	2189	0	PAVEMENT SEALER 4"	LF	30814			
	666	2191	0	PAVEMENT SEALER 8"	LF	9622			
ALT. NO.	ITEM NO.	DESC. CODE	S.P. NO	BID ITEM DESCRIPTION	UNIT OF MEASURE	APPROX. QUANTITIES	UNIT BID PRICE	AMOUNT	ITEM SEQUENCE NO.
	666	2195	0	PAVEMENT SEALER 24"	LF	4324			
	672	2012	34	REFL PAV MRKR TY I-C	EA	565			
	672	2015	34	REFL PAV MRKR TY II-A-A	EA	586			
	677	2001	0	ELIM EXT PAV MRK & MRKS (4")	LF	62530			
	677	2003	0	ELIM EXT PAV MRK & MRKS (8")	LF	813			
	677	2007	0	ELIM EXT PAV MRK & MRKS (24")	LF	452			
	680	2003	0	INSTALL HWY TRF SIG (SYSTEM)	EA	3			
	681	2001	0	TEMP TRAF SIGNALS	EA	3			
	682	2001	2	BACK PLATE (12 IN) (3 SEC)	EA	27			
	682	2002	2	BACK PLATE (12 IN) (4 SEC)	EA	3			
	682	2022	2	VEH SIG SEC (12 IN) LED (GRN ARW)	EA	11			
	682	2023	2	VEH SIG SEC (12 IN) LED (GRN)	EA	20			
	682	2024	2	VEH SIG SEC (12 IN) LED (YEL ARW)	EA	11			
	682	2025	2	VEH SIG SEC (12 IN) LED (YEL)	EA	20			
	682	2026	2	VEH SIG SEC (12 IN) LED (RED ARW)	EA	7			
	682	2027	2	VEH SIG SEC (12 IN) LED (RED)	EA	22			
	682	2044	2	PED SIG SEC (12IN)(2 INDICAT IN 1 SEC)	EA	8			
	684	2012	0	TRF SIG CBL (TY A) (12 AWG) (7 CONDR)	LF	1590			
	684	2035	0	TRF SIG CBL (TY A) (14 AWG) (9 CONDR)	LF	1003			
	686	2031	0	INS TRF SIG PL AM(S) 1 ARM (32')	EA	1			
	686	2035	0	INS TRF SIG PL AM(S) 1 ARM (36')	EA	2			
	686	2039	0	INS TRF SIG PL AM(S) 1 ARM (40')	EA	2			
	686	2047	0	INS TRF SIG PL AM(S) 1 ARM (48')	EA	3			
	686	2059	0	INS TRF SIG PL AM(S) 1 ARM (60')	EA	1			
	686	2063	0	INS TRF SIG PL AM(S) 1 ARM (65')	EA	1			
	688	2001	0	PED DETECT (2 INCH PUSH BTN)	EA	8			
	687	2001	0	PED POLE ASSEMBLY	EA	4			
	6041	XXXX	0	ILSN (LED)(8 D)	EA	10			
	6044	2001	0	VIVDS PROCESSOR SYSTEM	EA	6			

CITY OF SAN ANTONIO
025 UNIT PRICING FORM

PROJECT NAME:
PROJECT NO.

	6044	2002	0	VIVDS CAMERA ASSEMBLY	EA	21			
	6044	2003	0	VIVDS SET-UP SYSTEM	EA	3			
	6044	2005	0	VIVDS COMMUNICATION CABLE (COAXIAL)	LF	2613			
	6525	XXXX	0	EMERGENCY PREEMPTION PHASE SELECTOR	EA	3			
	6525	XXXX	0	EMERGENCY PREEMPTION DETECTOR	EA	10			
ALT. NO.	ITEM NO.	DESC. CODE	S.P. NO	BID ITEM DESCRIPTION	UNIT OF MEASURE	APPROX. QUANTITIES	UNIT BID PRICE	AMOUNT	ITEM SEQUENCE NO.
	6525	XXXX	0	EMERGENCY PREEMPTION DETECTOR CABLE	LF	1518			
	6834	2001	0	PORTABLE CHANGEABLE MESSAGE SIGN	DAY	29			
	8260	2001	0	LED COUNTDOWN PEDESTRIAN MODULE	EA	12			
	8261	2001	0	BATTERY BACKUP SYSTEM FOR TRAFFIC SIGNAL	EA	3			
	8245	XXXX	0	MODEL 2070 CONTROLLER UNIT	EA	3			
	8643	XXXX	0	TYPE 2070 CONTROLLER CABINET ASSEMBLY	EA	3			
	9501	XX01	0	MOBILIZATION (10%)	LS	1			
	9501	XX02	0	PREPARE ROW (5%)	LS	1			
	9501	XX03	0	TRENCH EXCAVATION PROTECTION	LF	5500			
	9501	XX04	0	8" PVC WATER MAIN (RESTRAINED)	LF	545			
	9501	XX05	0	12" PVC WATER MAIN	LF	4230			
	9501	XX06	0	16" PVC WATER MAIN	LF	585			
	9501	XX07	0	20" DI WATER MAIN	LF	140			
	9501	XX08	0	VALVE BOX ADJUSTMENT	EA	8			
	9501	XX09	0	8" GATE VALVE	EA	6			
	9501	XX10	0	12" GATE VALVE	EA	13			
	9501	XX11	0	16" GATE VALVE	EA	2			
	9501	XX12	0	20" BUTTERFLY VALVE	EA	1			
	9501	XX13	0	8" TIE-IN	EA	7			
	9501	XX14	0	12" TIE IN	EA	7			
	9501	XX15	0	16" TIE-IN	EA	1			
	9501	XX16	0	20" TIE-IN	EA	1			
	9501	XX17	0	FIRE HYDRANT ASSEMBLY	EA	7			
	9501	XX18	0	RELAY 3/4" SHORT SERVICE	EA	5			
	9501	XX19	0	RELAY 1" SHORT SERVICE	EA	1			
	9501	XX20	0	RELAY 1" LONG SERVICE	EA	1			
	9501	XX21	0	RELAY 2" SHORT SERVICE	EA	2			
	9501	XX22	0	PIPE FITTINGS	TON	15			

CITY OF SAN ANTONIO
025 UNIT PRICING FORM

PROJECT NAME:
PROJECT NO.

ALT. NO.	ITEM NO.	DESC. CODE	S.P. NO	BID ITEM DESCRIPTION	UNIT OF MEASURE	APPROX. QUANTITIES	UNIT BID PRICE	AMOUNT	ITEM SEQUENCE NO.
	9501	XX23	0	CASING OR LINER, 24"	LF	55			
	9501	XX24	0	HYDROSTATIC TESTING	EA	5			
	9501	XX25	0	2" BLOWOFF TEMPORARY	EA	14			
	9501	XX26	0	4" BLOWOFF TEMPORARY	EA	1			
	9501	XX27	0	2" BLOWOFF PERMANENT	EA	1			
	9501	XX28	0	TRENCH COMPLETION TYPE "A"	SY	313			
	9501	XX29	0	TRENCH COMPLETION TYPE "B"	SY	2115			
	9501	XX30	0	AC PIPE REMOVAL	LS	1			
	9501	XX31	0	AC PIPE REMOVAL PLAN	LS	1			
	9501	XX32	0	RECYCLED WATER VAULT RECONSTRUTION	EA	3			
	9501	XX33	0	RECYCLED WATER HYDRANT RELOCATION	EA	1			
	9501	XX34	0	FLOWABLE BACKFILL	CY	122			
	9501	XX35	0	ONCRETE ENCASEMENT, CRADLES, SADDLES & COLLA	CY	18			
	9500	XX01	0	MOBILIZATION (10%)	LS	1			
	9500	XX02	0	PREP ROW (5%)	LS	1			
	9500	XX03	0	ADJUST EXISTING MANHOLE	EA	16			
	9500	XX04	0	8" PVC SANITARY SEWER LINE (10' - 14')	LF	65			
	9500	XX05	0	SEWER MAIN TELEVISION INSPECTION	LF	1043			
	9500	XX06	0	SANITARY SEWER DROP MANHOLE (0' - 6')	EA	2			
	9500	XX07	0	EXTRA DEPTH MANHOLE (>6')	VF	11			
	9500	XX08	0	8" PVC SANITARY SEWER LINE (6' - 10')	LF	78			
	9500	XX09	0	SANITARY SEWER MANHOLE (0'-6')	EA	4			
	9500	XX10	0	SANITARY SEWER LATERAL	LF	180			
	9500	XX11	0	SANITARY SEWER CLEANOUT	EA	6			
	9500	XX12	0	BYPASS PUMPING	LS	1			
	9500	XX13	0	TRENCH COMPLETION CONDITION "B"	SY	93			
	9500	XX14	0	TRENCH COMPLETION CONDITION "C"	SY	20			
	9503	9001	0	NGP (SHORT SERV)(NEW MAIN TO PROP)	FT	1			
	9503	9003	0	NGP (SHORT SERV)(NEW MAIN TO METER)	FT	4			
	9503	9004	0	NGP (LONG SERV)(NEW MAIN TO METER)	FT	1			
	9503	9005	0	NGP (EXTEND)(PUMP TEST AND TIE TO METER)	FT	1			
	9503	9006	0	NGP (MAIN)(PLASTIC W/ TRACER)(2 IN)	FT	1000			
	9503	9007	0	NGP (MAIN)(PLASTIC W/ TRACER)(6 IN)	FT	2771			

CITY OF SAN ANTONIO
025 UNIT PRICING FORM

PROJECT NAME:
PROJECT NO.

	9503	9008	0	NGP (MAIN)(PLASTIC W/ TRACER)(8 IN)	FT	46			
	9503	9009	0	NGP (MAIN)(STEEL)(8 IN)	FT	142			
	9503	9010	0	NGP (MAIN)(STEEL)(16 IN)	FT	1104			
	9503	9011	0	NGP (MAIN)(STEEL)(16 IN) AND PLASTIC (6 IN)	FT	340			
	9503	9012	0	NGP (MAIN)(PLASTIC W/ TRACER)(2 IN)	FT	59			
	9503	9013	0	NGP (MAIN)(PLASTIC W/ TRACER)(6 IN)	FT	385			
	9503	9014	0	NGP (MAIN)(STEEL)(16 IN)	FT	100			
ALT. NO.	ITEM NO.	DESC. CODE	S.P. NO	BID ITEM DESCRIPTION	UNIT OF MEASURE	APPROX. QUANTITIES	UNIT BID PRICE	AMOUNT	ITEM SEQUENCE NO.
	9503	9015	0	TRENCH EXCAVATION PROTECTION	FT	5403			
	9503	9016	0	NGP (STOPPLE) (16IN)(TWD SERVICE)	EA	3			
	9503	9017	0	FLOWABLE BACKFILL	CY	390			
	9503	9018	0	ASPHALT	CY	460			
	9503	9019	0	MOBILIZATION	LS	1			

_____ certifies that the unit prices shown on this complete computer print-out for all of the bid items and the alternates contained in this proposal are the unit prices intended and that its bid will be tabulated using these unit prices and no other information from this print-out.

_____ Acknowleged and agrees that the total bid amount shown will be read as its total bid and further agrees that the official total bid amount will be determined by multiplying the unit bid prices shown in this print-out by the respective estimated quantities shown in the proposal and then totaling all of the extended amounts. _____ agrees to the terms, conditions, and requirements of the bidder's bid proposal.

Signed: _____ Date: _____

Title: _