ADDENDUM NO. 2

CITY OF SAN ANTONIO
AVIATION DEPARTMENT

PROJECT NAME: **San Antonio International Airport IT Infrastructure Modernization**

DATE: January 23, 2012

ADDENDUM NO. 2

This addendum shall be included in, and be considered a part of the plans and specifications for the above named project. The contractor shall be required to sign an Acknowledgment of the receipt of this Addendum, in the form attached hereto as Attachment A to Addendum No.2, and submit the Acknowledgement with their bid.

AVIATION PROJECT NO.: 33-00048

A. **QUESTIONS RECEIVED BY CITY STAFF IN ACCORDANCE WITH RFCSP SECTION 011 ARE ANSWERED AS FOLLOWS:**

1) On Sheet O-S0.00 Note 5 under the Drilled Pier heading states that unit prices for pier casing and greater and lesser depth are to be included with the bid documents. The bid form does not provide a space for these unit prices. Please provide a bid form that includes the pier unit prices.
Response: Disregard requirement for unit prices for pier casing and greater and lesser depth drilling.

2) Re: Detail 4/N1-A3.00- Is there any kind of ceiling being added to modular concrete building. It appears to look like plywood, just as the walls are to be lined. Please clarify.
Response: Reference specification section 133423, part 2.3.B, as indicated on the drawing, for ceiling information.

3) Re: Detail N1/C1.00- The fence specifically states to add PVT slats, but the gate does not. I referred to detail 8/O-C0.10, but it does not clarify. Please confirm that the owner also wants PVT slats on the gate at node 1.
Response: Correct. Provide PVT slats on the gate at node 1.

4) Re: N1-C1.00- please clarify if the fencing is supposed to include the spiral barbed wire in this area. The elevations for this fence do not indicate the spiral barbed wire in this area, however the general details for fencing does show this design. If the spiral barbed wire is to be included what is the overall of the fence.
Response: No. Spiral barbed wire not required for this fence.

5) Re: Detail 4/N2-A3.00- - Is there any kind of ceiling being added to modular concrete building. It appears to look like plywood, just as the walls are to be lined. Please clarify.
Response: Reference specification section 133423, part 2.3.B, as indicated on the drawing, for ceiling information.

6) Re: Note #12/N2-A2.00 & Note #4/N2-A3.00- States to provide a prefabricated ramp and railing as described in specification section 06 82 00- Fiberglass Reinforced Plastic Units. In section 1.8.A States to coordinate design with Systems Chemistry Inc. Was Systems Chemistry Inc. a consultant on this project, because I don't see any need to contact them regarding the project if the basis of design was Safe-T-Span of Fibergrate? Please confirm we do not need to contact Systems Chemistry Inc.
Response: Systems Chemistry Inc. was consulted in the development of design and specifications of this ramp. Specification indicates to "Coordinate **design** with Systems Chemistry, Inc." Bidders are free to determine extent of effort put into development of their bid.

7) Re: Detail 3/A4-A2.01. Please provide a wall type for the new east and south walls.
Response: A1 as indicated on Detail 2/A4-A2.00

8) Re: Detail 3/A4-A2.01. Please provide a wall detail on the west wall.
Response: No west wall detail will be provided. Wall will be similar to Wall type C (detail 4/O-AO.01), except wall finish material to be plywood instead of gypsum board. Continue wall base on this wall.

9) Re: Detail 3/A1-A2.01 and Detail 3/A1-S3.00. The Roof/Ceiling Details appear to be different as one of the details shows Densdeck sheathing and the other does not. Please clarify which detail to use for IDF 4.
Response: Use Detail 3/A1-A2.01 with Densdeck.

10) Re: Detail 3/D1-A2.00. Please confirm that <u>only</u> Room 2050 will receive new ceiling tiles and grids for IDF 5. The ceiling detail is misleading as to whether or not we are to put new ceiling where all of the grid appears.
Response: Correct. On sheet D1-A2.00, only IDF 5 is to receive new ceiling tiles and grid.

REGISTERED ARCHITECT
CARLA L. MARLEY
5540
STATE OF TEXAS

Carla L. Marley
January 23, 2012

ATTACHMENT A TO ADDENDUM NO. 2

Acknowledgement of Receipt of Addendum No. 2

CITY OF SAN ANTONIO
AVIATION DEPARTMENT

RECEIPT OF ADDENDUM NO. _2_ IS HEREBY ACKNOWLEDGED FOR PLANS AND

SPECIFICATIONS FOR CONSTRUCTION OF San Antonio International Airport IT Infrastructure Modernization – 33-00048

FOR WHICH BIDS WILL BE OPENED ON Tuesday, February 7, 2012 at 2:00 p.m.

THIS ACKNOWLEDGEMENT MUST BE SIGNED AND RETURNED WITH THE BID PACKAGE.

Company Name: _____

Address: _____

City/State/Zip Code: _____

Date: _____

_____
Signature

_____
Print Name/Title