## INDEX OF SHEETS

SHEET NO.

DESCRIPTION

TITLE SHEET

SUPPLEMENTAL INDEX

(NOTE: FOR ALL OTHER SHEETS SEE SUPPLEMENTAL INDEX)



REXAR StC1.

PERSONAL AND PROJECT NO.

CLASSIFICATION: NA DESIGN SPEED: NA AVERAGE DAILY TRAFFIC: NA AREA OF DISTURBED SOIL: LESS THAN 0.1 ACRE

FINAL PLANS

DATE CONTRACTOR BEGAN WORK:

FINAL CONTRACT COST: \$

## CITY OF SAN ANTONIO DEPARTMENT OF CAPITAL IMPROVEMENTS MANAGEMENT SERVICES

## SALADO CREEK BRIDGE

PROJECT NO.: 23-00904

LIMITS: CROSSING OVER SALADO CREEK PROJECT LENGTH: 0.059 MILES

LOCATION MAP

**END PROJECT** 

STA 510 + 40.00

"TDLR INSPECTION REQUIRED"

CITY OF SAN ANTONIO

APPROVED FOR LETTING:

CITY ENGINEER / DIRECTOR CAPITAL IMPROVEMENTS

MANAGEMENT SERVICES

"TDLR NO.:

LETTING DATE:

CONTRACTOR:

DATE WORK ACCEPTED:


BEGIN PROJECT -STA 507+30.00

PLANS PREPARED BY:



The seal appearing on this document was authorized by David M. McBeth P.E. 59223#

Tuntululm Pie



TRANSPORTATION, JUNE 1, 2004 AND SPECIFICATION ITEMS LISTED AND DATED AS FOLLOWS, SHALL GOVERN ON THIS PROJECT: REQUIRE CONTRACT PROVISIONS FOR ALL FEDERAL-AID CONSTRUCTION CONTRACTS (FORM FHWA 1273).(MARCH 1994)

SPECIFICATIONS ADOPTED BY THE TEXAS DEPARTMENT OF


## **INDEX OF SHEETS**


SHEET NO.		0.	DESCRIPTION						
			GENERAL						
	1		TITLE SHEET						
	2		SHEET INDEX						
	3		PROJECT LAYOUT						
	4		HORIZONTALCONTROL						
	5		TYPICAL CONCRETE SECTION						
6	-	9	GENERAL NOTES & SPECIFICATION DATA						
-	10		ESTIMATE & QUANTITIES						
			TRAFFIC CONTROL PLAN						
	11		NARRATIVE & SEQUENCE OF WORK						
			ROADWAY DETAILS						
12	-	14	PLAN & PROFILE SHEETS						
	15		ABUTMENT DESIGN						
16	-	19	BRIDGE DETAILS - CONTRACTOR'S INFORMATION						
			ENVIRONMENTAL ISSUES						
20	-	21	EC (1) -09, EC (2)-93						
	22		EPIC SHEET						

CITY OF SAN ANTONIO CAPITAL IMPROVEMENTS MANAGEMENT SERVICES DEPARTMENT

SALADO CREEK BRIDGE
INDEX SHEET

100 % SUBMITTAL PROJECT NO.: 23-00904 DATE: FEB 2012








## **CONCRETE TRAIL JOINT NOTES:**

Joints. Unless otherwise specified on plans or as agreed to by Engineer, tooled joints with rounded edges will be placed every ten feet (10') and will be opened with one-half inch (1/2") radius by one and one-half inch (1 1/2") depth and closed by one-half inch (1/2") radius by one-inch (1") depth.

- 1. Expansion Joints. Provide sidewalk sections separated by pre-molded or board joint 1/2" inch thick, or as shown on the plans, in lengths greater than 8 feet but less than 50 feet, unless otherwise directed. Terminate workday production at an expansion joint. Expansion joint material shall also be placed where the new construction abuts the existing curbs or driveways if the Engineer deems it necessary. The expansion joint material shall be placed vertically and shall extend the full depth and width of the concrete.
- 2. Expansion Joint Dowels. Unless otherwise shown own the plans, a minimum of two (2) round smooth dowel bars % inch in diameter and 18 inches in length of coating ends of dowels.







# **ENGINEERS**

SAN ANTONIO, TEXAS 78216 | PHONE: 210.375.9000 FAX: 210.375.9010



CITY OF SAN ANTONIO

TYPICAL SECTIONS & DETAILS

CONTROL SECTION JUB DIST. STATE COUNTY HIGHWAY NO. SHEET NO. 0915 12 375 SAT TX HEXAR

### GENERAL NOTES

- ALL CONSTRUCTION SHALL CONFORM TO THE CITY OF SAN ANTONIO STANDARD SPECIFICATIONS FOR CONSTRUCTION JUNE 2008, OR LATEST.
- NO EXTRA PAYMENT SHALL BE ALLOWED FOR WORK CALLED FOR ON THE PLANS, BUT NOT INCLUDED IN THE BID PROPOSAL THIS INCIDENTAL WORK WILL BE REQUIRED AND SHALL BE INCLUDED IN THE PAY ITEM TO WHICH IT RELATES.
- 3. THE CONTRACTOR SHALL PROVIDE ACCESS FOR THE DELIVERY OF MAIL BY THE U.S. POSTAL
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORING TO ITS ORIGINAL OR BETTER CONDITION ANY DAMAGE DONE TO EXISTING FENCES, CONCRETE ISLANDS, STREET PAVING, CURBS, SHRUBS, BUSHES OR DRIVEWAYS. (NO SEPARATE PAY ITEM).
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO SEE THAT ALL SIGNS AND BARRICADES ARE PROPERLY INSTALLED AND MAINTAINED, ALL LOCATIONS AND DISTANCES WILL BE DECIDED UPON IN THE FIELD BY THE CONTRACTOR, USING THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES". THE CITY'S CONSTRUCTION INSPECTOR AND TRAFFIC ENGINEERING REPRESENTATIVE WILL ONLY BE RESPONSIBLE TO INSPECT BARRICADES AND SIGNS, IF IN THE OPINION OF THE TRAFFIC ENGINEERING REPRESENTATIVE AND THE CONSTRUCTION INSPECTOR, THE BARRICADES AND SIGNS DO NOT CONFORM TO ESTABLISHED STANDARDS OR ARE INCORRECTLY PLACED OR ARE INSUFFICIENT IN QUANTITY TO PROTECT THE GENERAL PUBLIC, THE CONSTRUCTION INSPECTOR SHALL HAVE THE OPTION TO STOP OPERATIONS UNTIL SUCH TIME AS THE CONDITIONS ARE CORRECTED.
- IF THE NEED ARISES, ADDITIONAL BARRICADES AND DIRECTIONAL DEVICES MAY BE ORDERED BY THE TRAFFIC ENGINEERING REPRESENTATIVE AT THE CONTRACTOR'S EXPENSE.
- DUE TO FEDERAL REGULATIONS TITLE 49, PART 192.171 C.P.S. MUST MAINTAIN ACCESS TO GAS VALVES AT ALL TIMES. THE CONTRACTOR MUST PROTECT AND WORK AROUND ANY GAS VALVES THAT ARE IN THE PROJECT AREA.
- CONTRACTOR SHALL NOTIFY THE CITY INSPECTOR TWENTY FOUR (24) HOURS PRIOR TO BACKFILL OF ANY UTILITY TRENCHES TO SCHEDULE FOR DENSITY TEST AS REQUIRED.

233-2010

207-8048

207-7720 /207-7765

1-800-344-8377

- CONTRACTOR SHALL PRESERVE ALL CONSTRUCTION STAKES, MARKS, ETC. IF ANY ARE DESTROYED OR REMOVED BY THE CONTRACTOR OR HIS EMPLOYEES, THEY SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.
- 10. CONTRACTOR SHALL NOTIFY ALL UTILITY COMPANIES PRIOR TO CONSTRUCTION TO DETERMINE THE LOCATION OF EXISTING UTILITIES. CONTRACTOR SHALL NOTIFY THE FOLLOWING AT LEAST FORTY-EIGHT (48) HOURS PRIOR TO EXCAVATION OPERATION:

SAN ANTONIO WATER SYSTEM (SAWS) BEXAR METROPOLITAN WATER DISTRICT (BEXAR MET) 354-6538 /357-5741

COSA DRÁINAGE COSA SIGNAL OPERATIONS

TEXAS STATE WIDE ONE CALL LOCATOR

- CITY PUBLIC SERVICE ENERGY
- TIME WARNER
- AT&T - MCI
- 11. THE EXISTENCE AND LOCATION OF UNDERGROUND UTILITIES INDICATED ON THE PLANS ARE TAKEN FROM AVAILABLE RECORDS AND ARE NOT GUARANTEED, BUT SHALL BE INVESTIGATED AND VERIFIED BY THE CONTRACTOR BEFORE STARTING WORK THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR ANY DAMAGE TO AND FOR THE MAINTENANCE AND PROTECTION OF THE EXISTING UTILITIES EVEN IF THEY ARE NOT SHOWN ON THE PLANS LOCATION AND DEPTH OF EXISTING UTILITIES SHOWN HERE ARE APPROXIMATE ONLY. ACTUAL LOCATIONS AND DEPTHS MUST BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION AND HE SHALL BE RESPONSIBLE FOR PROTECTION OF SAME DURING CONSTRUCTION.
- 12. ALL WASTE MATERIAL SHALL BECOME PROPERTY OF THE CONTRACTOR AND SHALL BE HIS SOLE REPONSIBILITY TO DISPOSE OF THIS MATERIAL OFF THE LIMITS OF THE PROJECT. NO WASTE MATE-RIAL SHALL BE PLACED IN EXISTING LOWS THAT WILL BLOCK OR ALTER FLOW LIMITS OF EXISTING ARTIFICIAL OR NATURAL DRAINAGE.
- 13. THE CONTRACTOR SHALL NOT PLACE ANY WASTE MATERIAL IN THE 100-YEAR FLOOD PLAIN WITHOUT FIRST OBTAINING AN APPROVED FLOOD PLAIN DEVELOPMENT PERMIT.
- 14. THE CONTRACTOR SHALL MAINTAIN ALL ADJOINING STREETS AND TRAVELED ROUTES FREE FROM SPILLED AND /OR TRACKED CONSTRUCTION MATERIALS AND /OR DEBRIS.
- 15. IF THE CONTRACTOR ENCOUNTERS ANY ARCHAEOLOGICAL DEPOSITS DURING CONSTRUCTION OPERATIONS, THE CONTRACTOR MUST STOP EXCAVATION IMMEDIATELY, CONTACT THE CITY INSPECTOR, AND CALL THE CITY HISTORIC PRESERVATION OFFICE AT 207-7306 OR 207-3327 FOR AN ARCHAEOLOGICAL INVESTIGATION, THE CONTRACTOR CANNOT BEGIN EXCAVATION AGAIN WITHOUT WRITTEN PERMISSION FROM THE CITY.

IF MORE THAN THREE (3) DAYS ARE REQUIRED FOR INVESTIGATION (NOT INCLUDING HOLIDAY AND WEEKENDS) AND IF THE CONTRACTOR IS UNABLE TO WORK IN OTHER AREAS. THEN THE CONTRACTOR WILL BE ALLOWED TO NEGOTIATE FOR ADDITIONAL CONSTRUCTION TIME UPON WRITTEN REQUEST WITHIN TEN (10) DAYS AFTER THE FIRST NOTICE TO THE CITY OF ARCHAEOLOGICAL INVESTIGATION FOR EACH EVENT.

IF THE TIME REQUIRED FOR INVESTIGATION IS LESS THAN OR EQUAL TO THREE (3) DAYS FOR EACH EVENT, CONTRACT DURATION WILL NOT BE EXTENDED.

16. IF SUSPECTED CONTAMINATION IS ENCOUNTERED DURING CONSTRUCTION OPERATIONS, C.O.S.A. SHALL BE NOTIFIED IMMEDIATELY WHEN CONTAMINATED SOILS AND /OR GROUNDWATER ARE ENCOUNTERED AT LOCATIONS NOT IDENTIFIED IN THE PLANS. THE NOTIFICATION SHOULD INCLUDE THE STATION NUMBER, TYPE OF CONTAMINATED MEDIA, EVIDENCE OF CONTAMINATION AND MEASURES TAKEN TO CONTAIN THE CONTAMINATED MEDIA AND PREVENT PUBLIC ACCESS. THE CONTAMINATED SOIL AND /OR GROUNDWATER SHALL NOT BE REMOVED FROM THE LOCATION WITHOUT PRIOR C.O.S.A. APPROVAL,

THE CONTRACTOR MUST STOP THE EXCAVATION IMMEDIATELY AND CONTACT THE C.O.S.A. INSPECTOR. THE CONTRACTOR CANNOT BEGIN EXCAVATION ACTIVITIES WITHOUT WRITTEN PERMISSION FROM THE CITY.

17. CONTRACTOR IS TO INCLUDE A MAILBOX POST BLOCKOUT FOR VACANT LOTS AND ALL RESIDENCES WHICH DO NOT HAVE MAILBOXES AT THE CURB. BLOCKOUTS ARE PROVIDED FOR FUTURE USE BY THE POST OFFICE.

18. CONTRACTOR SHALL NOT REMOVE OR ADJUST ANY VIA FACILITIES. THE CONTRACTOR MUST CONTACT VIA FOURTEEN DAYS PRIOR, FOR THE REMOVAL OF BENCHES, STOP POLES OR ANY OTHER VIA FACILITIES THAT MAY BE PRESENT. PLEASE PROVIDE THIRTY DAYS PRIOR NOTICE FOR SHELTER REMOVAL (TELEPHONE NOS: (210) 362-2155 OR (210) 362-2096). THE CONTRACT-OR WILL BE LIABLE FOR ANY DAMAGES TO VIA FACILITIES NOT REMOVED BY VIA. THE CON-TRACTOR IS REQUIRED TO REPLACE ALL FLATWORK REMOVED OR DAMAGED IN THE COURSE OF EXECUTING THE CONTRACT UNLESS OTHERWISE NOTED BY VIA. THE CONTRACTOR WILL BE RESPONSIBLE FOR PROTECTING VIA FACILITIES IF ADJACENT TO WORK AREA.

## TREE PROTECTION AND PRESERVATION GENERAL NOTES

- 1. NO UTILITY OR STREET EXCAVATION WORK SHALL BEGIN IN AREAS WHERE TREE PRESERVATION AND TREATMENT MEASURES HAVE NOT BEEN COMPLETED AND APPROVED.
- 2. TREE PROTECTION FENCING SHALL BE REQUIRED. TREE PROTECTION FENCING SHALL BE INSTALLED, MAINTAINED AND REPAIRED BY THE CONTRACTOR DURING SITE CONSTRUCTION. DURING CONSTRUCTION ACTIVITY, AT LEAST A SIX-INCH LAYER OF COARSE MULCH SHALL BE PLACED AND MAINTAINED OVER THE ROOT PROTECTION ZONE (NO SEPARATE PAY ITEM).
- 3. THE CONTRACTOR SHALL AVOID CUTTING ROOTS LARGER THAN ONE INCH IN DIAMETER WHEN 'EXCAVATING NEAR EXISTING TREES. EXCAVATION' IN THE VICINITY OF TREES SHALL PROCEED WITH CAUTION THE CONTRACTOR SHALL CONTACT THE CITY INSPECTOR FOR GUIDANCE
- 4. ROOTS WILL BE CUT WITH A ROCK SAW OR BY HAND, NOT BY AN EXCAVATOR OR OTHER ROAD CONSTRUCTION EQUIPMENT.
- ALL CURB AND SIDEWALK WORK SHALL USE ALTERNATIVE CONSTRUCTION METHODS TO MINIMIZE EXTENSIVE ROOT DAMAGE TO TREES (REFER TO DETAILS).
- EXPOSED ROOTS SHALL BE COVERED AT THE END OF THE DAY USING TECHNIQUES SUCH AS COVERING WITH SOIL, MULCH, OR WET BURLAP.
- 7. NO EQUIPMENT, VEHICLES OR MATERIALS SHALL OPERATE OR BE STORED WITHIN THE ROOT PROTECTION ZONE OF ANY TREE NEAR THE PROJECT, ROOT PROTECTION ZONE IS 1 FOOT OF RADIUS PER INCH OF TREE'S DIAMETER, A 10-INCH DIAMETER TREE WOULD HAVE A 10 FOOT RADIUS ROOT PROTECTION ZONE AROUND THE TREE ROOTS OR BRANCHES IN CONFLICT WITH THE CONSTRUCTION SHALL BE CUT CLEANLY ACCORDING TO PROPER PRUNING METHODS. OAK WOUNDS SHALL BE PAINTED OVER WITHIN 30 MINUTES TO PREVENT
- SAPLINGS, SHRUBS OR BUSHES TO BE CLEARED FROM THE PROTECTED ROOT ZONE AREA OF A LARGE TREE SHALL BE REMOVED BY HAND AS DESIGNATED BY THE INSPECTOR.
- NO WIRES, NAILS OR OTHER MATERIAL MAY BE ATTACHED TO PROTECTED TREES.
- 10. TREES, TREE LIMBS, BUSHES AND SHRUBS LOCATED IN THE CITY STREET OR ALLEY RIGHT-OF-WAY OR PERMANENT EASEMENTS WHICH INTERFERE WITH PROPOSED CONSTRUCTION ACTIVITIES SHALL BE PROPERLY PRUNED FOLLOWING THE ANSI A-300 STANDARDS FOR PRUNING. ALL TREE PRUNING SHALL BE COMPLETED BY A CITY OF SAN ANTONIO TREE MAINTENANCE LICENSED CONTRACTOR (ARTICLE 21-171, CITY CODE) ONLY AFTER APPROVAL FROM THE CAPITAL PROJECTS MANAGEMENT THROUGH THE INSPECTOR.
- 11. NO EXCESSIVE TREE TRIMMING WILL BE PERMITTED.
- 12. ALL DEBRIS GENERATED BY THE PRUNING AND TRIMMING OF THE TREES AND /OR BUSHES SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE DISPOSED OF PROPERLY (NO SEPARATE PAY ITEM).
- 13. TREES MUST BE MAINTAINED IN GOOD HEALTH THROUGHOUT THE CONSTRUCTION PROCESS MAINTENANCE MAY INCLUDE, BUT NOT LIMITED TO: WATERING THE ROOT PROTECTION ZONE, WASHING FOLIAGE, FERTILIZATION, PRUNING, ADDITIONAL MULCH APPLICATIONS AND OTHER MAINTENANCE AS NEEDED ON THE PROJECT
- 14. ANY TREE REMOVAL SHALL BE APPROVED BY THE CITY ARBORIST. (207-0278)
- 15. TREES WHICH ARE DAMAGED OR LOST DUE TO THE CONTRACTOR'S NEGLIGENCE DURING CONSTRUCTION SHALL BE MITIGATED TO THE CITY'S SATISFACTION.
- TREE PLANTING FOR MITIGATION OR ENHANCEMENT: ALL PLANTED TREES SHALL BE MAINTAINED IN A HEALTHY CONDITION AT ALL TIMES. THIS INCLUDES IRRIGATION, FERTILIZING, PRUNING AND OTHER MAINTENANCE AS NEEDED ON THE PROJECT. TREES THAT DIE WITHIN TWELVE (12) MONTHS SHALL BE REPLACED WITH A TREE OF EQUAL SIZE AND SPECIES.

## ACCESSIBILITY REQUIREMENTS

- 1. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN VEHICULAR AND PEDESTRIAN ACCESS AT ALL TIMES TO LOCAL RESIDENCES AND BUSINESSES.
- WHEN THE WORK REQUIRES THE EXCAVATION OF THE STREET AND THE REMOVAL OF THE EXISTING DRIVEWAY APPROACHES AND SIDEWALKS THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING TEMPORARY ALL-WEATHER ACCESS TO THE BUSINESSES AND RESIDENCES. THE TEMPORARY DRIVEWAY APPROACHES SHALL BE CONSTRUCTED WITH FLEXIBLE BASE OR GRAVEL MATERIAL AT NO SEPARATE COST TO THE CITY.
- PRIOR TO INITIATING THE CONSTRUCTION OF NEW DRIVEWAY APPROACHES, THE CONTRACTOR SHALL GIVE ADVANCE WARNING IN PERSON, OR IN WRITING, OF AT LEAST 48 HOURS TO EACH RESIDENCE THAT WILL BE IMMEDIATELY AFFECTED, SO THAT ALTERNATE PLANS MAY BE MADE
- FOR BUSINESSES WITH MORE THAN ONE DRIVEWAY, AT LEAST ONE DRIVEWAY SHALL REMAIN OPEN WHILE THE OTHER NEW DRIVEWAY APPROACHES ARE CONSTRUCTED. FOR BUSINESSES WITH ONLY ONE DRIVEWAY, THE NEW DRIVEWAY APPROACH SHALL BE CONSTRUCTED IN HALF WIDTHS, UNLESS A TEMPORARY ASPHALT DRIVEWAY IS FIRST INSTALLED AT NO SEPARATE COST TO THE CITY.

## DECEMBER 2009

CITY OF SAN ANTONIO CAPITAL IMPROVEMENTS MANAGEMENT SERVICES DEPARTMENT

CITY OF SAN ANTONIO GENERAL NOTES

% SUBMITTAL PROJECT NO.

## THE FOLLOWING CHANGES ARE MADE TO THE CITY OF SAN ANTONIO'S GENERAL NOTES:

## ADDITIONAL NOTES

TREE PROTECTION AND PRESERVATION GENERAL NOTES.

17.AFTER THE CONTRACTOR EVALUATES THE EXISITNG TREES AND DETERMINES THAT CLEARING OR TRIMMING IS REQUIRED TO ASSEMBLE AND SET THE BRIDGE, CONTACT THE ENGINEER TO COORDINATE A FIELD MEETING WITH THE CITY ARBORIST PRIOR TO COMMENCING WORK.

## NOTE MODIFICATION

1. MODIFY NOTE NO. 1 - TXDOT 2004 SPECIFICATIONS

CONSULTANT NAME
STREET NUMBER AND ADDRESS
CITY , STATE ZIP CODE
FAX NUMBER

CITY OF SAN ANTONIO CAPITAL IMPROVEMENTS MANAGEMENT SERVICES DEPARTMENT

PROJECT TITLE

SUPPLEMENTAL GENERAL NOTES

% SUBMITTAL PROJECT NO.:\_

Project Number: 23–00904 County: Bexar General Notes Sheet A

- G-5 To better fit field conditions, the cross sections may be varied when approved.
- G-6 If there are waste areas or material source areas, follow the Texas Aggregate Quarry and Pit Safety Act requirements.
- G-7 Any materials removed and not reused and determined to be salvageable shall be stored within the project limits at an approved location or delivered undamaged to the storage yard as directed. Properly dispose unsalvageable materials in accordance with local, state, and federal regulations. Deface traffic signs so that they will not reappear in public as signs.
- 5–4B. The earthwork information was not developed with computers; therefore, a CD can not be provided. Prior to letting, earthwork cross–sections will be available at the Engineer's office for review by the bidder or for borrowing by copying companies to make copies at the bidder's expense.
- 5–5 When working near aerial electrical lines or utility poles, comply with Federal, State and local regulations. For electrical lines and poles shown in the plans, if the lines need to be de-energized or if poles need to be braced, contact the electrical company. Work pertaining to de-energizing lines, bracing poles and other protective measures will not be paid by TxDOT or the City of San Antonio.

5-6 Prevention of Migratory Bird Nesting

It is anticipated that migratory birds, a protected group of species, may try to nest on bridges, culverts, vegetation, or gravel substrate, at any time of the year. The preferred nesting season for migratory birds is from February 15 through October 1. When practicable, schedule construction operations outside of the preferred nesting season. Otherwise, nests containing migratory birds must be avoided and no work will be performed in the nesting areas until the young birds have fledged

Structures

Bridge and culvert construction operations can not begin until swallow nesting prevention is implemented, until after October 1 if it's determined that swallow nesting is actively occurring, or until it's determined swallow nests have been abandoned. If the State installed nesting deterrent on the bridges and culverts, maintain the existing nesting deterrent to prevent swallow nesting until October 1 or completion of the bridge and culvert work, whichever occurs earlier. If new nests are built and occupied after the beginning of the work, do not perform work that can

Project Number: 23–00904 County: Bexar General Notes Sheet B

interfere with or discourage swallows from returning to their nests. Prevention of swallow nesting can be performed by one of the following methods:

1. By February 15 begin the removal of any existing mud nests and all other mud placed by swallows for the construction of nests on any portion of the bridge and culverts. The Engineer will inspect the bridges and culverts for nest building activity. If swallows begin nest building, scrape or wash down all nest sites. Perform these activities daily unless the Engineer determines the need to do this work more frequently. Remove nests and mud through October 1 or until bridge and culvert construction operations are completed.

2. By February 15 place a nesting deterrent (which prevents access to the bridge and culvert by swallows) on the entire bridge (except deck and railing) and culverts.

No extension of time or compensation payment will be granted for a delay or suspension of work

caused by nesting swallows. This work is subsidiary to the various bid items.

-Item 5-

5–7 Use Provide a non-intrusive back-up alarm system on all heavy equipment used in close proximity to if work is residential areas. This item is subsidiary to various bid items. required in residential areas.

—Item 6—

6-1 Show the stockpile lot and/or sub lot numbers on all tickets for all materials.

—Item 7—

- 7–2 The total disturbed areas within the project is anticipated at less than one (1) acre. Due to this type of construction, the project qualifies for exclusion under the Construction General Permit (CGP) issued by the Texas Commission on Environmental Quality (TCEQ) on March 5, 2008. However, should the sum of the Engineer\*s anticipated disturbances and the Contractor\*s (On ROW and off ROW) PSL\*s equal or exceed the one (1) acre threshold; both TxDOT and the Contractor have project responsibilities under the CGP that reverts to non–exclusion status. Obtain approval for all non–depicted areas of disturbance that increases the initial soil and vegetation disturbed area estimates before work starts at these locations.
- 7-3 Notify the Engineer of the disturbed acreage within one (1) mile of the project limits. Obtain authorization from the TCEQ for Contractor PSL\*s for construction support activities on or off ROW.

---Item 8----

8–2 The number of working days and interim milestones, if any, were calculated using a conceptual time determination schedule that assumes generic resources, production rates, sequences of construction and average weather conditions based on historic data. If requested, the Engineer

CITY OF SAN ANTONIO
CAPITAL IMPROVEMENTS MANAGEMENT SERVICES DEPARTMENT

SALADO CREEK BRIDGE

GENERAL NOTES TXDOT

100 % SUBMITTAL PROJECT NO: 23-00004 DATE: FEB 2012

DRWN, BY: BFT DSGN, BY: BFT CHKD, BY: DMM SHEET NO: OF

Project Number: 23–00904 County: Bexar General Notes Sheet C

will supply bidders a CD of the time determination schedule compatible with Primavera Project Planner software. The time determination schedule is provided for informational use only and is not intended for bidding or construction purposes. If the schedule is used for bidding or construction purposes, the bidder accepts the schedule and assumes the responsibility for verifying all aspects of the schedule. The department will not adjust the number of working days and milestones, if any, due to differences in opinion regarding any assumptions made in the preparation of the schedule or for errors, omissions or discrepancies found in the schedule. 8–2A

-Item 9-

9-1 When approved, provide uniformed, off-duty law enforcement officers with marked vehicles during work that requires a lane closure. The officer in marked vehicles shall be located as approved to monitor or direct traffic during the closure. The method used to direct traffic at signalized intersections shall be as approved. Additional officers and vehicles may be provided when approved or directed.

Complete the daily tracking form provided by the department and submit invoices that agree with the tracking form for payment at the end of each month approved services were provided. Minimums, scheduling fees, etc. will not be paid; TxDOT will consider paying cancellation fees on a case by case basis.

-ltem 420-

420-1 Mass concrete will be measured in place.

420-2 Restrict large aggregate size to \*\* maximum for class \*C\* concrete used in aesthetic details requiring form liners.

-ltem 500-

500--1 "Materials on Hand" payments will not be considered in determining percentages for mobilization payments.

-- Item 502-

502-1 Place standard markings no later than 14 days after surface treatment operations are completed.

502-4 After written notification, the time frame to provide properly maintained signs and barricades before considered in non-compliance is 48 hours from receipt of the notification.

Project Number: 23–00904 County: Bexar General Notes Sheet D

502–8 Notify the Engineer 5 business days in advance of any temporary or permanent lane, ramp, connector, etc. closures/detours, restrictions to lane widths, alterations to vertical clearances, or modifications to radii. Any other modifications to the roadway that may adversely affect the mobility of oversized/overweight trucks also require 5 business days advance notice to the Engineer. Unless shown in the TCP, no lane, ramp, connector, etc. closures are allowed during special events. At least one lane has to remain open at all times. For all lane closures, provide written closure information by 1:00PM on the business day prior to the closure. For closures on a Monday or following a Holiday, furnish the information the workday prior to the closure. Lane closures will not be allowed if this reporting requirement is not met. 502–11 In addition to providing a Contractor's Responsible Person and a phone number for emergency contact, have an employee available to respond on the project for emergencies and for taking corrective measures within 2 hours or within a reasonable time frame as specified by the

CITY OF SAN ANTONIO
CAPITAL IMPROVEMENTS MANAGEMENT SERVICES DEPARTMENT

SALADO CREEK BRIDGE

GENERAL NOTES TXDOT

 100
 %
 SUBMITTAL
 PROJECT NO.:
 23-00904
 DATE:
 FEB 2012

 DRWN. BY:
 BFT
 DISN. BY:
 BFT
 CHKD. BY:
 DMM
 SHEET NO.:
 OF

## ROADWAY SUMMARY

100	110	132	160	164	168	416
2002	2001	2003	2003	2027	2001	2002
PREPARING ROW	EXCAVATION (ROADWAY)	EMBANKMENT (FINAL) (ORD COMP) (TYP A)	FURNISHING AND PLACING TOPSOIL	CELL FBR MLCH SEED (PERM)(URBAN) (CLAY)	VEGETATIVE WATERING	DRILL SHAFT (24IN)
STA	CY	CY	SY	SY	MG	LF
3.0	500.0	1,125.0	100.0	1,605.0	25.0	148.0

420	420	442	454	500	502	752
2003	2003 2045		2004	2001	2001	2022
CL C CONC (ABUT)	1 1		ARMOR JOINT	MOBILIZATION	BARRICADES, SIGNS, TRAFFIC HANDLING	TREE REMOVAL (4"-12" DIA)
CY	SY	LS	LF	LS	MO	EA
9.7	377.0	1.0	24.0	1.0	2.0	20.0

CITY OF SAN ANTONIO
CAPITAL IMPROVEMENTS MANAGEMENT SERVICES DEPARTMENT

SALADO CREEK BRIDGE

ROADWAY SUMMARY

 100 %
 SUBMITTAL PROJECT NO.:
 23-00904
 DATE:
 FEB 2012

 DRWN. BY:
 BFT
 DSGN. BY:
 BFT
 CHKD. BY:
 DMM
 SHEET NO.:
 1 OF 1

## SALADO CREEK BRIDGE PROJECT

## SEQUENCE OF CONSTRUCTION WORK

## General:

- 1. Install barricades and traffic control devices in accordance with the TMUTCD. Place barricades at each entrance to the project site to deter the public from entering the construction zone.
- 2. Contractor to work within the existing cleared trail in as much as possible. If additional clearing is required for this project, please notify the Engineer for prior approval.
- 3. Contractor will clean up and remove from the work area all loose material or trash resulting from the construction operations at the end of each work day.
- 4. Contractor will not be allowed to stage materials along the existing hike and bike trail outside of the project limits. Staging area location shall be coordinated with Engineer prior to commencing work.
- 5. Contractor shall plan and submit a staging, assembly and bridge placement plan and submit to the Engineer within 30 days of the notice to proceed.

## Sequence of Work:


- 1. Initiate shop drawing preparations for pre-fabricated steel bridge
- 2. Obtain approval of shop drawings.
- 3. Initiate bridge fabrication
- 4. Install needed SWPPP BMP's for erosion control.
- 5. Install barricades and traffic control devices.
- 6. Construct concrete bridge abutments.
- 7. Perform as built survey of abutments for conformance with bridge dimensions.
- 8. Perform rough grading and compaction of trail subgrade profiles.
- 9. Prepare staging area for bridge delivery and assembly.
- 10. Delivery of bridge and assembly.
- 11. Set steel bridge on abutments, complete installation.
- 12. Place reinforcement and pour concrete decking on bridge.
- 13. Final subgrade preparation on trail connections.
- 14. Construction of remaining concrete trail connections.
- 15. Topsoil and seeding of disturbed areas, water until 70% vegetation established.
- 16. Clean up site and prepare for final inspection.


CITY OF SAN ANTONIO
CAPITAL IMPROVEMENTS MANAGEMENT SERVICES DEPARTMENT


SALADO CREEK BRIDGE NARRITIVE SEQUENCE OF WORK


 100 % SUBMITTAL
 PROJECT NO.: 23-00904
 DATE: FEB 2012


 DRWN. BY: BFT
 DSGN. BY: BFT
 CHKD. BY: DMM
 SHEET NO.: 1 OF 1















## 1 BRIDGE ELEVATION



4 DETAIL

SCALE: 3/4"=1'-0"

# 2 BRIDGE ABUTMENT PLAN

- PLAN NOTES:

  1. ALL CONCRETE SHALL HAVE A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF 4000 PSI.
- ALL REINFORCING SHALL BE ASTM A615 GRADE 60. ALL REBAR BENDS SHALL CONFORM TO CURRENT ACI
- DETAILING REQUIREMENTS.
- ALL DRILLED SHAFTS SHALL BEAR IN GRAY CLAY.






Bridge Abutment Plan and Details Salado Creek Pedestrian Bridge Crossing #2 LAM Salado Phase 1 San Antonio, Texas

SCALE: AS SHOWN CONT.:

FEGAL W. Neal & Assoc., Inc. 1115 W. Boulday, Forward, Teas 7819 817302 1544, 6-13-0072009 Tenss Certificate of Authorization No. F-000296
PROJECT NO.:
2110908
SHEET NO.: S 1 DATE: 06/29/11 SECT.: S1

-1" JOHNT CONT. L3x3x3/8 W/ 3/8"x4" LONG H.S. 9 12" O.C. MAX. FLATWORK AND ARMOR-JOINT EMBED BY OTHERS BRIDGE ABUTMENT NOTE: HEADED STUDS AND ANGLES SHALL BE HOT DIP GALVANIZED AFTER WELDING STUDS TO ANGLES.

> ARMOR JOINT ENBED DETAIL SCALE: 1 1/2"=1'-0"




# SIDE VIEW - BEARING ASSEMBLY





THESE PLANS, AS INSTRUMENTS OF SERVICE ARE PROPERTY SOLELY OF CONTECH BRIDGE SOLUTIONS INC. THEY ARE NOT TO BE REPRODUCED FOR ANY PURPOSE OR USED IN ANY OTHER LOCATION WRITHOUT WRITTEN AUTHORIZATION.

OF CONTECT BRIDGE
IS INC. THEY ARE NOT TO
ODUCED FOR ANY PURPOSE
IN ANY OTHER LOCATION
OF THE LOCATION
OF THE








THESE PLANS, AS INSTRUMENTS OF SERVICE ARE PROPERTY SOLELY OF CONTECH BRIDGE SOLUTIONS INC. THEY ARE NOT TO BE REPRODUCED FOR ANY PURPOSE OR USED IN ANY OTHER LOCATION WITHOUT WRITTEN AUTHORIZATION.

THEY ARE NOT TO OR ANY PURPOSE OTHER LOCATION PEDESTRIAN BRIDGE




# <u>PLAN - BEARING ASSEMBLY</u>





THESE PLANS, AS INSTRUMENTS OF SERVICE ARE PROPERTY SOLELY OF CONTECH BRIDGE SOLUTIONS INC. THEY ARE NOT TO BE REPRODUCED FOR ANY PURPOSE OR USED IN ANY OTHER LOCATION WITHOUT WRITTEN AUTHORIZATION.

NOT TO JRPOSE CATION PEDESTRIAN BRIDGE







THESE PLANS, AS INSTRUMENTS OF SERVICE ARE PROPERTY SOLELY OF CONTECH BRIDGE SOLUTIONS INC. THEY ARE NOT TO BE REPRODUCED FOR ANY PURPOSE OR USED IN ANY OTHER LOCATION WITHOUT WRITTEN AUTHORIZATION.

PEDESTRIAN BRIDGE

## SECTION A-A

## GENERAL NOTES

 The guidelines shown hereon are suggestions only and may be modified by the Engineer.

## PLAN SHEET LEGEND

Sediment Control Fence




## SEDIMENT CONTROL FENCE USAGE GUIDELINES

A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.

Sediment control fence should be sized to filter a max, flow through rate of 100 GPM/FT . Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.


Galv. Hinge joint knot woven mesh (12.5 Ga. Min.) requires a minimum of five horizontal wires spaced at a max.12 inches apart and all vertical wires spaced at a max. 12 inches apart.



## Hinge Joint Knot Woven Mesh (Option)

Connect the ends of successive reinforcement sheets or rolls a min, of 6 times with hog rings.

Galv. Welded wire mesh (W.W.M.) with a max. opening size of 2"x 4", or Woven Mesh (W.M.) (See Detail)




## TEMPORARY SEDIMENT CONTROL FENCE



# 3:1 Max. Overlap tops of Hay Bales Angle stakes Loward adjacent bale

## PLAN VIEW



PROFILE VIEW

## PLANS SHEET LEGEND

oled Hay ----




## BALED HAY USAGE GUIDELINES

- A Baled Hay installation may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A two year storm frequency may be used to calculate the flow role to be filtered. The installation should be sized to filter a maximum flow thru rate of 5 GPM/FT<sup>2</sup> of cross sectional area. Baled hay may be used at the following locations:
  - Where the runoff approaching the baled hay flows over disturbed soil for less than .100°. If the slope of the disturbed soil exceeds 10%, the length of slope upstream the baled hay should be less than 50°.
- Where the installation will be required for less than 3 months.
- Where the contributing drainage area is less than ½ acre.


For Baled Hay installations in small ditches, the additional following considerations apply:

- The ditch sideslopes should be graded as flot as possible to maximize the drainage flowrate thru the hay.
- The ditch should be graded large enough to contain the overtopping drainage when sediment has filled to the top of the baled hay.

Bales should be replaced usually every 2 months or more often during wet weather when loss of structural integrity is accelerated.



## SECTION B-B



## GENERAL NOTES


- Hay bales shall be a minimum of 30" in length and weigh a minimum of 50 Lbs.
- Hay boles shall be bound by either wire or nylan or polypropylene string. The bales shall be composed entirely of vegetative matter.
- 3. Hoy boles shall be embedded in the soit a minimum of 4" and where possible  $\frac{1}{2}$  the height of the bole.
- Hay bales shall be placed in a row with ends tightly abutting the adjacent bales. The bales shall be placed with bindings parallel to the around.
- 5. Hay bales shall be securely anchored in place with 3/8" Dia, rebar or 2" x 2" wood stakes, driven through the bales. The first stake shall be angled towards the previously loid bale to force the bales together.
- The guidelines shown hereon are suggestions only and may be modified by the Engineer.



POLLUTION CONTROL MEASURES
FENCE & BALED HAY

EC(1)-09

FQ.E:	TxDOT :NG		CK: AM DW:		TV ck: BD			
© TxDOT June 1993			CONT	ONT SECT JOB		HIGI	HIGHWAY	
RE VISIONS					_			
			DIST	· · ·	COUNTY		5	SHEET NO.
				-				20




SEE NOTE 6

Galvanized Woven Wire Mesh

(for Types 2 & 3)

## FILTER DAM AT CHANNEL SECTIONS

Width for payment



## **GENERAL NOTES**

- If shown on the plans or directed by the Engineer, filter dams should be placed near the toe of slopes where erosion is anticipated, upstream and/or downstream of drainage structures, and in roadway ditches and channels to collect sediment.
- Moterials (aggregate, wire mesh, sandbags, etc.) shall be as indicated by the specification for "Rock Filter Dams for Erosion and Sedimentation Control".
- The rock filter dom dimensions shall be as indicated on the SW3P plans.
- 4. Side slopes should be 2:1 or flatter. Dams within the safety zone shall have sideslopes of 6:1 or flatter.
- Mointain a minimum of t between top of rock filter dom weir and top of embankment for filter dams at sediment traps.
- Filter dams should be embedded a minimum of 4" into existing ground.
- The sediment trap for ponding of sediment laden runoff shall be of the dimensions shown on the plans.
- 8. Rock filter dam types 2 & 3 shallbe secured with 20 gauge galvanized woven wire mesh with 1" diameter hexagonal openings. The aggregate shall be placed on the mesh to the height & slopes specified. The mesh shall be folded at the upstream side over the aggregate and tightly secured to itself on the downstream side using wire ties or hag rings. In stream use the mesh should be secured or staked to the stream bed origin to convente alconomia.
- 9. Sock Gobions should be stoked down with 34" dia, rebor stokes.
- Flow outlet should be onto a stabilized area (vegetation, rock, etc.).
- The guidelines shown hereon are suggestions only and may be modified by the Engineer.



TEMPORARY EROSION,
SEDIMENT AND WATER
POLLUTION CONTROL MEASURES

ROCK FILTER DAMS

EC(2)-93

ice: ec293.0gn	IDOL IXOO	CK: HEJ DW	LIBD CK:
C) Tx00T June 1993	CONT SE		HIGHWAY
REVISIONS			
	DIST	COUNTY	SHEET NO.
			21

Ministration   Participate		L Stormwoler Poliution Prevention	- Clean Woter Act Section 402		III. Cultural Resources	-		V	. Hozordous Moterials or Contamination	n Issues			
and the baseline.    The contract between   Property of the pr	TPDES TXR 150000: Stormwater Discharge Permit or Construction General Permit required for			Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are			İ	General (applies to all projects):					
No Asire Register   10 A									***	on Act (the Act) for personnel who v	wili be working with hazardous		
In a lark the base of   Depart from   Depa		protect for erosion and segmentation in accordance with item 206.			etc.) cease work in the initinearate area and contact the Engineer Immediately.								
Add to the control of the control			<b>57</b>				<b>G</b>		· ·	•	with personal protective		
Action to  Life the processing which the minimizary data the minimizary data the minimizary data and minimizary data the minimizary data and minimizary data the minimizary data the minimizary data and minimizary data the minimizary data and minimizary data the minim	ı	No Action Required			No Action Required		Required Action				ardous products used on the		
1. The contraction and to complete the contraction of the contraction	ı	Action No.			Action No.			1	project, which may include, but are no	'ilmited to the following categories	s: Paints, acids, solvents,		
of the first hand for table 2. Oncy, the Fig. 3 and response in the present of th	ı												
2. Compared to the position of the contract part of	ı		cordance										
In a liquid.  In the Control of the Section of the			onwart bur					Mointain an adequate supply of on-site spill response materials, as indicated in the MSDS. In the event					
1. The Contractive part of the first contribution of a contributio	ı	• •	titles recessory to control bookton or te	quied by									
S. The Contractive principle quartity services desired services and the principle quartity services and the pr	ı				2.				procinces, and contact the District Spill Coordinator Immediately. The Contractor shall be responsible for the proper containment and cleanup of all product soills.				
Less that comment performs to the control of the following control of t	ı	l de la companya de											
The Contract and Collect for Times, confidence and services and servic		occessible to the public and TCEO, (	EPA or other inspectors.		İ				Contact the Engineer It any of the fo	liwing are detected:			
** Ann. If or and Sisterine, Restriction and Billionian Class their Act Section  **ORGAT Product regulator for It Tilling, engage, countries or or and every finite and production or all or word in day and braiding parallels.    In Product Product or and the control of an additional countries and the control or and the regulatory parallels.	ı	4. When Controctor project specific loc	cations (PSL's) increase disturbed soil are	eo lo 5				l					
Exposite for the process of the street of contribution of the time and contribution of contribution of the time and contribution of	1	acres or more, submit NOI to TCEO	and the Engineer.							arrels,elc.			
### Action Processed for a failing-designed parameter of a controlled parameter of a failing-designed parameter of a controlled parameter of the processed of the failing-designed parameter of the controlled parameter of the co		•	-						1 11 11 11 11 11 11 11 11 11 11 11 11 1				
## Preserve affolion seguration of the many of controlling or cont	ı,	I, Work in or near Streams, Waterbo	odes and Wellands Clean Water A	Act Sections	IV. Vegetation Resources								
We Action Regulated for College Confidence Control C	l	4018 404	•	·		— inn to the ext	ieni praeticai		Any other evidence indicating possible hazardous materials or contamination discoverd on site.				
The Controdor and others to all of the tones and conditions associations with the following parameters    In the head Register   In the Register   In the Intended on one of the Head Register   In the Intended on one of the Head Register   In the Intended on one of the Head Register   In the Intended on one of the Head Register   In the Intended on one of the Head Register   In the Intended on one of the Head Register   In the Intended on one of the Head Register   In the Intended on one of the Head Register   In the Intended on one of the Head Register   In the Intended on one of the Head Register   In the Intended on one of the Head R				ork in any water bodies, rivers,		UN TO THE GATE	•		Hazardous Materials or Conta	mination Issues Specific to this Pr	ro ject:		
Set New No.   Set No.	Š	creeks, streams, wetlands or wet a	reas.		☐ No Action Required		Required Action				•		
See North Regard   Indicate Proof 14 - Pits at Departed lates the YOB nore value or wetlood distance   Indicate Provide Name	Š	The Contractor must adhere to all	of the terms and conditions assoc	tated with the following permit(s):	Action No			-	No Action Required	Required Action			
Simple from the project of the final form form of the project of the final from the final from				•	Control 1409				Action No.				
Controlled Front 18 - PCR Regarded VD to 472 core; US is bidd selected   Controlled Front Regarded State   Controlled Front Regarded Reg	5				1. Every effort will be made	to prederve t	the natural vegetation within the project limits.		170.1011 710.				
Control From Regulate   Three   Thre	9	_							1.				
Deer Notionale Promit Regions 1800 (See 1800	ı	_	red (1/10 to (1/2 ocre, 1/3 in biddi woter	rs)	2.				_				
Property Actions tail not till germin qualities in, scooles in project and cases   Post Minesperson Projections in the till germinal project and cases   Post Minesperson Projections   Post October Projection	l		MAD		,				2.				
Required Actional bits states of the US growth deplies in scaled in graphical and control fields in surprised fields.  1. An instantial originating trans a STACL productional state within use which the project field.  2. In originating trans a STACL productional state within use which the project field.  3. Control fields are also as a state of the Action Required Action  4. Control fields are also as a state of the Action Required Action  Action Re.  Ercolan  Section Scalinariation  Post Construction TSS    Improvery Vegetation   Share   Improvery Vegetation   Share the Control fields are also as a state of the Action Regulate State (action of the Action Regulate Action   Action Re.   Improvery Vegetation   Share   Improvery Vegetation   Share the		Comments of the state of the st			J				7		•		
Les methodoles in control design in the color of the process to control design, interfection and process and the process of the color of the color of the process of the color of t	l				4.				<b>3.</b>				
Z in an updated once, an indicated in 1990. jurisdictional section.    No.   Post Conference of Conference of Species, Confidence Species, Confide				•	-			1	4		•		
State Listed Species, Condition Species and Migratory Birds.    Control Fire Dem on Social   Section Register   Social Response of the Desire Control Compact   Mach Fire Dem on Social   Social Response of the Desire Control Compact   Mach Fire Dem on Social   Compost Fire Dem	ı	1. Any material originating from a USACE jurisdictional water will be used within the project limits.		N. Sadarati in a contract of the contract of t				<del></del>					
No Action Required New York production received:   No Action Required								VI	Other Environmentalissues				
No Action Required   Required Action   No Action Required   Required Action   No Action Required   Required Action   No Action No	ı	4- in an upland area, no material is to be	e ploced in USACE jurisdictional waters.					<b>.</b>	lincludes regionalissues such as Edw	ords Aquifer District, etc.)	et.		
Action No.    Best Management Practices	ľ	3.					_		•				
Best Management Practices  Erosion Setimentation Post-Construction TSS   Temporary Vegetation   Past Enem   Vegetative Filter Stripe   Souther Harding   Past Enem   Receivable Private Past Past Berns   Past Berns					☐ No Action Required		Required Action	ı	No Action Required	Required Action			
Best Management Practicass    Erostion   Sedimentation   Post Construction TSS   Temporary Vegetation   Safferce   Vegetative Filter Strips   Share Extended Detention Bosin   Sociation   Stree Bear and Sociation Compact   Stree Bear and Sociation Compact   Stree Bear and Sociation Compact   Stree Bear and Sociation   Compost Filter Bern and Sociation		4.	•		Action No.				Action No.	,			
Best Management Practicess    Erostion   Sedimentation   Post Construction TSS     Temporary Vegetation   Set Fince   Vegetative Filter Strips     Busnets/Marting   Rock Bern   Retembor/regions Systems   Retembor/regions of the Brighteen Intendicions of the Systems   Retembor/regions of the Systems   Retembor/regio	ı				. D								
Erosion Sedimentation   Temporary Vegetation   Sedimentation   Past-Construction TSS     Temporary Vegetation   Sed Fence   Vegetable Files Strips     Boukets / Matrix incompose Filer Dike   Extended Detention Bosin     Sodding   Sodd Boy   Strate Bode   Bette Bosin     Sodding   Sodd Boy   Strate Bode   Bette Bosin   Constructed Wetlands     Strate Bode   Strate Bode   Bette Bosin   Constructed Wetlands     Strate Bode   Strate Bode   Bette Bosin   Constructed Wetlands     Strate Bode   Strate Bode   Bette Bosin   Control Compost     Erosion Coutral Compost   Erosion Control Compost	ı	· · · · · · · · · · · · · · · · · · ·		· · · · · · · · · · · · · · · · · · ·	I -				1,				
Temporary Vegetation   Set Fence   Vegetative Filter Strips   Retention Unrigidate Systems   Retention Virgidate Systems   South Berms   Constructed Methods   Tricomplor Filter Dise   Extended Detention Boois   Store Bole Dise   Retention Virgidate Systems   Store Bole Dise   Retention Virgidate Systems   Constructed Methods   Retention Virgidate Systems   Store Bole Dise   Retention Virgidate Systems   Construct Compost   Extended Detention Boois   Compost Filter Berm and Socks		Best Management Practices:			_				2				
Temporary Vegetation   Six Ferce   Vegetative Filter Strips   South Basins   Retention/trigation Systems   South gas Barm   Constructed Wetands   Maker Filter Barm and Socks   South Barms   Prosinc Control Compost   Maker Filter Barm and Socks   South Barms   Consol Filter Barm and Socks   Compost Filter Barm and Socks   Compost Filter Barm and Socks   Vegetation Liked Ditches   South Filter Barm and Socks   Vegetation Liked Ditches   South Filter Systems   South Filter Sy		Fracina	Sadimentation	Pact Coarte attac TCC					<b>4.</b>	•			
Gentpoor's Yegetation   Set Fence   Yegetation False Strps     Gentpoor's Yegetation   Set Fence   Yegetation Systems     Gooding   Soud Bog Berm   Constructed Weltonds     Giversion Date   Stross Bode Date   Het Bosin   Erosion Control Compost   Watch Filter Berm and Socks   Compost Filter Berm and Socks   Compost Filter Berm and Socks   Compost Filter Berm and Socks   Yegetation Lined Ditches   Yegetation Systems     Gooding   Soud Bog Berm   Constructed Weltonds   Transportation     Gisting Dutylson   Design Dutylson   Design Dutylson     Gentpoor's Yegetation   Yegetation Systems   Transportation     Gisting Dutylson   Design Dutylson   Design Dutylson     Gentpoor's Yegetation   Yegetation Systems   Transportation     Gisting Dutylson   Design Dutylson   Design Dutylson   Design Dutylson     Gentpoor's Yegetation   Transportation   Transportation     Gisting Dutylson   Design Dutylson   Design Dutylson   Design Dutylson     Gentpoor's Yegetation   Transportation   Design Dutylson   Design Dutylson     Gentpoor's Yegetation   Transportation   Transportation   Design Dutylson     Gentpoor's Yegetation   Transportation   Transportation   Transportation   Transportation   Design Dutylson   Desi		_			to the structure to prev	ent future nest	building.		3.	<u>.</u>			
Mulch   Triongular Filter Dike   Extended Detention Bosin   Sooding   Sond Bog Berm   Constructed Wetlands   Wet Basin   Wet Basin   Texas Department of Transportation   Design Division   De		<b>-</b> · / /	<del>_</del>	<del></del>			•		<del></del>				
Sodding Sodding Sond Bog Berm Constructed Wetlands Met Bosin Interceptor Seale Stross Bote Dike Wet Bosin Division Dike Stross Bote Dike Stross Bote Dike Stross Bote Dike Stross Control Compost Design Division Control Compost Stross Control Compost Stross Control Compost Stross Control Compost Stross Control Compost Stross Control Compost Stross Control Compost Stross Control Compost Filter Berm and Socks Compost Filter Berm and Socks Stross Stross Compost Filter Berm and Socks Stross Compost Filter Berm and Socks Stross Socks Stross		_		4.				4.	•				
Interceptor Sincile   Diversion Dike   Brush Berms   Erosion Control Compost   Erosion Control Compost   Erosion Control Compost   Erosion Control Compost   Mulch Filter Berm and Socks   Compost Filter Berm and Socks   Compost Filter Berm and Socks   Vegetotion Lined Ditches   Stone Quite! Sediment Traps   Sond Filter Systems      Stone Quite! Sediment Basins   Sediment Basins   Sirone Basins   Wet Basin   Wet Basin   Wet Basin   Design Division   Design Div	ı	<del></del>											
Diversion Dike   Brush Berms   Erosion Control Compost   Erosion Control Compost   Erosion Control Compost   Mutch Filter Berm and Socks   Compost Filter Be			<del></del>	_				l		Texas Depai	riment of Transportation		
Erosion Control Compost		_	land.	_						_ Doory	in Districti		
Mulch Filter Berm and Socks   Mulch Filter Berm and Socks   Compost Filter Berm and Socks   Vegetotion Lined Ditches   Compost Filter Berm and Socks   Vegetotion Lined Ditches   Stone Outlet Sediment Traps   Sond Filter Systems   Sediment Basins   Sediment Basin		<u> </u>	_	<del>_</del>				1.		Environmento	l Permits.		
Compost Filter Berm and Socks Composit Filter Berm and Socks Compo		_		<b>-</b>	habitat and contact the E	Engineer imm	rediately. The work may not remove active nests from bridges and	_   `			·		
Stone Outlet Sediment Traps			_					re		lissues and C	ornmitments		
EPIC  FLE: epic.dgn	1	<del></del>	<b>—</b>								2.0		
© TXDOT May 2010 CONT SECT JOB HSCHWAY  REVISIONS 23-00904  OST COUNTY SHEET NO.	1									[ E	JIC.		
© TXDOT May 2010 CONT SECT JOB HSCHWAY  REVISIONS 23-00904  OST COUNTY SHEET NO.	1												
REVISIONS 23-00904 OST COUNTY SHEET NO.	ľ												
										REVISIONS	23-00904		
	ij,	,											

SHEET NO.