



PLAN NOT TO SCALE NOTE: CONCRETE SHALL BE 3000 PSI, MIN, AND REINFORCED WITH NO. 4 BARS, AS SHOWN.

THE CONCRETE SHALL EXTEND TO EDGE OF SAWCUT PAVEMENT EDGE.

## CITY OF SAN ANTONIO

DEPARTMENT OF PUBLIC WORKS

COSA TASK ORDER CONTRACT
MANHOLE/VALVE BOX ADJUSTMENTS

MANHOLE/VALVE BOX
CONCRETE ENCASEMENT DETAIL

% SUBMITTAL	PROJECT NO. :12	0-11175-061	DATE: APR-2011
DOWN BY	DSGN. BV	CHKD. BV: ISD	SHT / 1 AF 1