

ADDENDUM NO. 2

CITY OF SAN ANTONIO
CAPITAL IMPROVEMENTS MANAGEMENT SERVICES

PROJECT NAME: 2013 EDA Task Order Contract Package 7

DATE: 11/28/2012

ADDENDUM NO. 2

This addendum should be included in and be considered part of the plans and specifications for the name of the project. The contractor shall be required to sign an acknowledgement of the receipt of this addendum and submit with their bid.

CIMS PROJECT NO.: 23-01304



-
1. Note to Contractors per pre bid meeting:
 - a. Contractor shall furnish all truck tickets for asphalt as provided by the material supplier(s). The following information will be printed on each ticket by the supplier: date, time, amount (in tons), and street name where the materials will be used. Each ticket must be submitted to City officials.
 2. Add the following special provision
 - a. Item 502 Concrete Sidewalks (502.1A Handicap Ramps)

** Addenda Acknowledgement Form for Addendum 2 is attached herein. This form must be signed and submitted with the bid package.

SPECIAL PROVISION Item 502 Concrete Sidewalks

For this project, Item 502 "Concrete Sidewalks" of the Standard Specifications is hereby amended with respect to the clauses cited below, and no other clauses or requirements on the Item are waived or changed hereby.

Article 502.4. Construction. G. Curb Ramps. This paragraph is void and replaced with the following:

Curb ramps must include a detectable warning surface and conform to the details shown on the plans. Confirm that abrupt changes in sidewalk elevation do not exceed ¼ inch, sidewalk cross slope does not exceed 2%, curb ramp grade does not exceed 8.3%, and flares adjacent to the ramp do not exceed 10% slope.

Construct curb ramps to include the following provisions:

- Construct detectable warning surface with truncated domes conforming to the City of San Antonio Wheelchair Ramp Standards sheet.
- Remove existing flatwork in accordance with the specification for Item 103, except measurement and payment.
- Construct new curb in accordance with the specification for Item 500, except measurement and payment.
- Construct concrete retaining wall (combination type), up to a maximum height of 6 inches, in accordance with the specification for Item 506, except measurement and payment.
- Adjust or relocate existing signs as directed.
- Contractor shall not leave the ramp unattended more than 1 day.
- Concrete work shall be free from graffiti of any kind.
- Relocate irrigation systems in accordance with the specification for Item 552, except measurement and payment.
- Contractor shall deliver flyers at least 2 days in advance.
- Relocate landscape as directed.
- Avoid damage to the property of others. Contractor will be held liable for damage.

Article 502.5. Measurement. This paragraph is void and replaced with the following:

Sidewalks will be measured by the square yard of surface area at the depth specified.
Curb ramps will be measured by the square yard of surface area or by each unit, as specified in the plans.

When measured by the square yard of surface area, curb ramps will consist of the curb ramps of the type specified in the plans, landings, adjacent flares or side curb as shown in the plans, detectable warning surface, concrete retaining wall (combination type up to 6" in height), sign adjustment or relocation, irrigation relocation, landscape relocation, delivery of flyers, and graffiti removal.

When measured by "each unit", each curb ramp unit will consist of one curb ramp of the type specified in the plans, removal of existing flatwork, one landing and up to two wings, one detectable warning surface, new curb, concrete retaining wall (combination type up to 6" in height), concrete surfaces up to a maximum of 14 square yards, sign adjustment or relocation, irrigation relocation, landscape relocation, delivery of flyers, and graffiti removal.

Article 502.6. Payment. The following paragraph is added:

When curb ramps are noted in the plans to be measured by "each unit", the work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Curb Ramps". Concrete surface for a curb ramp exceeding 14 SY will be paid as Concrete Sidewalk per square yard. When concrete retaining wall (combination type) is needed to exceed 6 inches in height, it shall be measured and paid for in accordance with Item 506.

Article 502.7. Bid Item. The following paragraph is added:

Item 502.1A – Curb Ramps – Each

**CITY OF SAN ANTONIO
DEPARTMENT OF CAPITAL IMPROVEMENTS MANAGEMENT SERVICES
CONTRACT SERVICES DIVISION**

RECEIPT OF ADDENDUM NUMBER(S) 2 IS HEREBY ACKNOWLEDGED FOR PLANS AND

SPECIFICATIONS FOR CONSTRUCTION OF 2013 EDA Task Order Contract Package 7

FOR WHICH BIDS WILL BE OPENED ON TUESDAY, DECEMBER 4, 2012 AT 2:00 P.M.

THIS ACKNOWLEDGEMENT MUST BE SIGNED AND RETURNED WITH
THE BID PACKAGE.

Company Name: _____

Address: _____

City/State/Zip Code: _____

Date: _____

Signature

Print Name/Title